


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

RXXK Finney County. Sec. 27 Twp. 21 Rge. 31W (E) (W)  
Location as "NE/CNW/SW" or footage from lines CE/2 W/2 NW  
Lease Owner Bennett & Roberts Drilling Co.  
Lease Name Rayl Well No. 1  
Office Address Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4/30 19 56  
Application for plugging filed 7/13 19 56  
Application for plugging approved 7/16 19 56  
Plugging commenced 7/14 19 56  
Plugging completed 7/16 19 56  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2780 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	311'	None
				5 1/2"	2780'	975'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 2700', dumped 5  
sax cement at 2700', top of cement 2665. Filled  
hole with mud to 305', set rock bridge, dumped 20  
sax cement. Top of cement 240'. Filled with mud  
to 35', set rock bridge, dumped 10 sax cement for cap.

RECEIVED  
JUL 22 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Miller Casing Pulling Co. 7-20-56  
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of July, 19 56

My commission expires 6/17/58

Clara Lumme  
Notary Public.

PLUGGING  
FILE SEC 27 T 21 R 13W  
BOOK PAGE 80 LINE 13

Bennett & Roberts Drilling Co.  
Rayl #1

CE/2 W/2 NW 27-21-31  
Finney County, Kansas

R.T.D. 2780'

8 5/8" @ 311 w/200 sx cmt.  
5 1/2" @ 2780 w/300 sx cmt.

Commenced 4/25/56  
Completed 4/30/56

-----Figures Indicate Bottom of Formation-----

Top Soil & Clay	40
Sand	190
Sand, Grv. & Clay	280
Blue Shale	312
Shale & Shells	850
Sandy Shale & Shells	1210
Blue Shale & Shells	1300
Red Shale & Shells	1565
Shale & Shells	2440
Lime & Shale	2780

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.

I hereby acknowledge that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By *Quis Lake*

Subscribed and sworn to before me this 22nd day of May, 1956.

*Clara Hummel*  
Notary Public

My Commission Expires 6/17/58

PLUGGING			
FILE	SEC. 27	T. 21	R. 01W
BOOK	PAGE 80	LINE	13

FILED  
STATE CORPORATION COMMISSION

JUL 16 1956

CONSERVATION DIVISION  
Wichita, Kansas