

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,259-0000

LEASE NAME F.N.B. of Hutchinson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR American Warrior, Inc.

SEC. 18 TWP. 21 RGE. 31W (E) or (W)

ADDRESS P. O. Box 399 Garden City, KS 67846

COUNTY Finney

PHONE (316) 275-2963 OPERATORS LICENSE NO. 4058

Date Well Completed

Character of Well Oil

Plugging Commenced 3-18-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-18-97

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 2740'

Show depth and thickness of all water, oil and gas formations.

3-27-97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	353'	none
				4 1/2"	2736'	700'

RECEIVED
KANSAS CORP
1997 MAR 27 AM 11:40

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Halliburton pumped 200# hulls & 20 sks cement down to plug bottom. Plug did not hold. Pumped another 300# hulls & 20 sks cement. Plug held. Shot csg at 1400' & pumped 70 sks cement w/150# hulls. Shot at 700', pumped 40 sks cement. Pulled to 350 & pumped 40 sks cement. Pulled rest of pipe & topped with 10 sks cement. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 97

Notary Public

My Commission Expires:

