

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 17 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE/4

Lease Owner M. B. Armer

Lease Name Arthur De Roo Well No. 1

Office Address 710 Petroleum Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed Dec. 3 1952

Application for plugging filed Dec. 3 1952

Application for plugging approved Dec. 3 1952

Plugging commenced Dec. 3 1952

Plugging completed Dec. 3 1952

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3896 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	995'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary Mud 300 ft.

Set plug and ran 20 sacks cement through

drill pipe. Filled with mud to 35', set

plug and 10 sacks cement at the surface.

12-10-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer

Address 710 Petroleum Bldg., Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. C. Sponenberg (employee of owner) or (owner/conservator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address) _____

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 52

My commission expires Sept. 17, 1955.

Hazel Watson
Notary Public.

PLUGGING
FILE SEC 17 T 21 R 1624
BOOK PAGE 63 LINE 25

L O G

Company: M. B. Armer
 Contractor: M. B. Armer (Ideco Rig)
 Drilling Commenced: 11/18/52
 Drilling Completed: 12/3/52
 Elevations: 1999 D.F.
 2001 K.B.

Farm: De Roo #1
 Location: SW SW SE
 Sec. 17-21S-16W
 Pawnee County, Kans.
 Casing Record: 8-5/8" casing at
 995' with 450 sacks cement.

(figures below indicate bottoms)

Surface Clay	140
Sand	150
Shale	405
Sand	535
Red Bed, Shale & Shells	860
Red Bed & Shale	980
Anhydrite	1020
Red Bed, Shale & Shells	1185
Shale & Shells	1850
Broken Lime	2110
Lime & Shale	2205
Shale, Lime & Shells	2350
Shale & Lime	2465
Shale & Shells	2625
Shale & Lime	3580
Lime	3720
Shale & Lime-Chert	3787
Shale	3797
Sand	3802
Lime	3855
Lime & Chert	3877
Lime	3896
R.T.D.	3896

FORMATION TOPS (R.B. Meas.)

HEEBNER	3364
BROWN LIME	3454
LANSING-KANSAS CITY	3464
CONGLOMERATE	3781
SIMPSON SHALE	3787
SIMPSON SAND	3796
ARBUCKLE	3802

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

RECEIVED
 STATE CORPORATION COMMISSION

By

STATE OF KANSAS

COUNTY OF SEDGWICK

DEC 10 1952
 CONSERVATION DIVISION
 Topeka, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 8th day of December, 1952.

Harold D. Dalton
 Notary Public

My Commission Expires: Sept. 17, 1955.

