

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 23 Twp. 21S Rge. 16 ~~W~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Leben Drilling, Inc.

Lease Name Lawton Well No. 1

Office Address 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-17-57 19

Application for plugging filed 7-17-57 19

Application for plugging approved 7-17-57 19

Plugging commenced 7-17-57 19

Plugging completed 7-17-57 19

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt, Russell, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	986'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 350' w/ 1/2 sx hulls, rock bridge, & 20 sx cement.
2nd Plug @ 40' w/ 1/2 sx hulls, 10 sx cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July, 1957

My commission expires June 17, 1961

Ruth N. Benjamin
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
7-26-57
JUL 26 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23 T. 21 R. 16w
BOOK PAGE 30 LINE 2

CONTRACTOR'S WELL LOG

COMPANY:	LEBEN DRILLING INC.
CONTRACTOR:	LEBEN DRILLING INC.
FARM:	LAWTON NO. 1
LOCATION:	NW NW NW SEC. 23 21S 16W, PAWNEE COUNTY, KANSAS
COMMENCED:	7-2-57
COMPLETED:	7-17-57

			TOPS	
0	98	Sand		
98	205	Sand		
205	280	Shale Sand & Shells	Heobner	3365
280	290	Pyrite	Toronto	3380
290	398	Shale	Douglas	3399
398	640	Sand	Brown Lime	3457
640	865	Red Bed	Lansing	3466
865	978	Shells & Red Bed	Base Kansas City	3711
978	986	Anhydrite	Viola	3746
986	995	Lime	Simpson	3799
995	1375	Shale	Arbucklo	3853
1375	1640	Shale & Shells		
1640	1830	Shale & Lime		
1830	1965	Shale & Lime		
1965	2060	Shale & Lime		
2060	2180	Lime & Shale		
2180	2255	Shale & Lime		
2255	2295	Lime		
2295	2380	Lime & Shale		
2380	2465	Shale & Lime		
2465	2615	Shale & Shells		
2615	2820	Shale & Lime		
2820	2970	Shale & Lime		
2970	3180	Lime & Shale		
3180	3314	Shale & Lime		
3314	3360	Lime & Shale		
3360	3398	Lime		
3398	3458	Lime & Shale		
3458	3460	Brown Lime		
3460	3521	Lime		
3521	3598	Lime		
3598	3635	Lime		
3635	3695	Lime & Shale		
3695	3790	Lime		
3790	3853	Shale		
3853	3860	Dolomite		
	3860	ROTARY TOTAL DEPTH	D & A	

Set 8 5/8" surface casing @ 986' w/450 sacks cement & 6 sacks CaCl & 4 sacks gel.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lawton #1, NW NW NW of Section 23, Township 21 South, Range 16 West, Pawnee County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: Frank Hamlin
Frank Hamlin

STATE OF KANSAS) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of July, 1957.

Ruth G. Benjamin
Ruth G. Benjamin, Notary Public
CORPORATION COMMISSION

My Commission expires June 17, 1961.

PLUGGING
FILE SEC. 23 T. 21 R. 16W
BOOK PAGE 30 LINE 2

JUL 26 1957

ION DIVISION
a, Kansas