


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 9 Twp. 16 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner W. O. Johnson
Lease Name Turgeon Well No. 3
Office Address P. O. Box 218, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 13 1976
Application for plugging filed February 13 1976
Application for plugging approved February 13 1976
Plugging commenced February 13 1976
Plugging completed February 13 1976
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3321 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 500' w/40 sacks cement thru drill pipe.
Mud to 250' w/25 sacks Cement thru drill pipe.
Mud to 40' w/2 sacks hulls plug and 10 sacks cement.
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1976

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke Drilling Co. CONSERVATION DIVISION
Address Box 823, Great Bend, Kansas 67530 Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON
Larry Curtis (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Ks.

Subscribed and sworn to before me this 16th day of February 1976

My commission expires April 11, 1978
Dorothy M. Hogue Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: February 18, 1976
DATE COMPLETED: February 13, 1976

W. O. Johnson
TURGEON # 3
SW NW NW of Sec 9-T16-R12 W
Barton County, Kansas

ELEVATION: 1870 K.B.

FORMATION TOPS

0 - 180' Surface Soil, Post Rock & Shale
180 - 252' Red Bed
252 - 480' Shale and Sand
480 - 795' Red Bed and Shale
795 - 820' Anhydrite
820 - 1460' Shale
1460 - 2550' Lime and Shale
2550 - 2667' Shale and Shells
2667 - 2947' Lime
2947 - 2950' Shale
2950 - 2961' Lime and Shale
2961 - 2977' Lime
2977 - 3033' Shale
3033 - 3048' Lime and Shale
3048 - 3300' Lime
3300 - 3321' Lime, Shale, Chert, Sand
3321' RTD

Anhydrite 795
Topeka 2667
Heebner 2947
Toronto 2961
Douglas 2977
Brown Lime 3033
Lansing K.C. 3048
Cong. 3300
RTD 3321

SURFACE PIPE:

Set 252' of used 8 5/8",
28# pipe w/175 sacks Common,
2% Gel, 3% cc.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 16th day of February, 1976.

Dorothy M. Hague
Notary Public

My Commission Expires: April 11, 1978.

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1976

CONSERVATION DIVISION
Wichita, Kansas