

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 5-009-21,295-00-00

LEASE Turgeon Turgeon

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Petroleum Energy

SEC. 9 TWP. 16S RGE. 12 (E or W)

ADDRESS Kress Energy Center, 224 E. Douglas, Suite
350, Wichita, Kansas 67202

COUNTY Barton

PHONE# (316) 265-2661 OPERATORS LICENSE NO. 5230

Date Well Completed

Character of Well oil

Plugging Commenced 11-18-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11:00AM

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #4

Is ACO-1 filed? YES if not, is well log attached?

Producing Formation Depth to Top 3347 Bottom 3349 T.D. 3347

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Contented	From	To	Size	Put in	Pulled out
				8 5/8	436	2128.05
				5 1/2	3347	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom: 5 sacks cement, sand
top 5 hulls, 200 cement, 800/550

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 768, Great Bend, Kansas

Subscribed and sworn to before me this 22 day of November, 1988

Louella L. Mullen
 Notary Public

My Commission Expires: 1-13-90
 NOTARY PUBLIC - State of Kansas
 LOVELLA L. MULLEN
 My Appt. Exp. 1-13-90

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 28 1988
 WICHITA, KANSAS

Drillers' Well Log

DATE COMMENCED: December 15, 1977
DATE COMPLETED: December 24, 1977

Petroleum Energy, Inc.
TURKON #1
NW SW SW
Sec. 9-T16S-R12W
Barton County, Kansas

ELEVATION: 1902 F.B.

0	100'	Clay & Post Rock
100	436'	Shale - Streaks of Sand
436	755'	Shale - Red Bed
755	801'	Shale
801	829'	Anhydrite
829	1529'	Shale
1529	2963'	Shale & Lime
2963	2968'	Shale
2968	2973'	Lime & Shale
2993	3060'	Shale & Lime
3060	3312'	Lime
3312	3329'	Lime & Shale
3329	3949'	Shale - Lime, Sand RTD

Formation Data

ANHYDRITE	801
HERRINER	2963
DOUGLAS	2993
LANSING	3060
CONGLOMERATE	3329
RTD	3349

SURFACE PIPE: Set used 3 1/2" 28' pipe at 436' with 250 sacks common cement, 25 gal. salt per ft.

PRODUCTION PIPE: Set now 5 1/2" 14# casing at 3312' with 125 sacks common cement, salt per ft. with 10 bbls. salt flush ahead.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 29 th day of December 1977.

My Comm. Expires: April 11, 1978

Alvoretta M. Hague
Notary Public