

15-009-30914-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 9 Twp. 16 Rge. 12 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE SW NW

Lease Owner National Cooperative Refinery Association

Lease Name Turgeon "A" Well No. 3

Office Address 820 Union National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 15, 1952

Application for plugging filed June 16, 1952

Application for plugging approved June 16, 1952

Plugging commenced June 16, 1952

Plugging completed June 16, 1952

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3318 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	241.55	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240', set plug, dumped 40 sxs. cement. Filled hole w/heavy mud to 35', set plug, dumped 20 sxs. Cement on up to base of cellar. Cement settled to 40', filled hole with heavy mud to 10', dumped 5 sacks cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company

Address Hays, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

W. Jean La Coss (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean La Coss

820 Union National Bank Building

(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of June, 1952

My commission expires February 20, 1953

I. A. Lange Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1952

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9-16-18W
BOOK PAGE 24 LINE 4

24-2675-B 2-52-20M

6-18-52

DRILLING LOG

Lease: #3 Turgeon "A"

County: Barton
 Location: SE SW NW
 Section: 9-16S-12W
 Elevation: 1800' KB

Rotary Total Depth: 3318'
 Commenced: June 4, 1952
 Completed: June 16, 1952
 Casing: 8-5/8" @ 237' w/140 sacks of cement and 2 sacks of calcium chloride

CONTRACTOR: John Lindas Oil, Inc.
 1316 Union National Bank Bldg.
 Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0 to	237	Shale & Shells
237	375	Shale
375	535	Shale & Shells
535	785	Red Bed
785	815	Anhydrite Lims
815	1150	Shale
1150	1250	Shale
1250	1550	Shale Shells
1550	2110	Lime & Shale
2110	2595	Shale & Shells
2595	2630	Shale
2630	2710	Lime & Shale
2710	2805	Lime
2805	2869	Lime & Shale
2869	2945	Lime
2945	3035	Shale
3035	3242	Lime
3242	3290	Hard Lime
3290	3318	Lime
	3318	TD

STATE OF KANSAS)
) SS
 COUNTY OF SELWICK)

I, the undersigned, being duly sworn on oath state that the above statement and log is a true and correct record of the well drilled by John Lindas Oil, Inc. at the location above described.

Edward W. Wiers

Subscribed and sworn to before me this 17th day of June, 1952.

Catherine Lacey
 Notary Public

My commission expires: March 25, 1956

RECEIVED
 STATE CORPORATION COMMISSION

JUN 19 1952

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FILE SEC 9-T-16-R

BOOK PAGE 24 LINE 7

ORDER OF THE COURT

[Handwritten signature]

IN WITNESS WHEREOF

[Circular stamp]