


STATE OF KANSAS
CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 9 Twp. 16 Rge. 12 (E) (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines. CEL SW-SE
Lease Owner. Black Marshall Oil Co.
Lease Name. J.P.Mans Well No. 1
Office Address. Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
Date well completed. March 30, 1945
Application for plugging filed. March 31 1945
Application for plugging approved. April 5 1945
Plugging commenced. April 8, 1945 19
Plugging completed. April 12, 1945 19
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. None 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H.W.Kerr
Producing formation. None Depth to top. Bottom. Total Depth of Well. 3367' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
✓				8 5/8"	225'	Cemented
✓				5 1/2"	3347'	2626' 7"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run 5-Sack of Cement in bottom, Filled the hole with heavy mud to 200', Bridged the hole at 200' and run 15- sacks of cement on top of Bridge, then heavy mud to 25', Set Bridge and run 10-Sacks of cement to bottom of cellar, and cemented cellar.

4-24-45

PLUGGING
FILE 9-16212W
BOOK PAGE 9 LINE 5



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Black Marshall Oil Co.
Address. Claflin, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Walter C Roberts (employee of owner) or (owner/operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter C Roberts
Claflin, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 1945.
Edwin Wojdzjak Notary Public.
My commission expires February 5, 1947

COMPANY: Black-Marshall Oil Co.
 CONTRACTOR: Hannum Drilling Co.

FARM: J. P. Mans
 LOCATION: CEL SW SE 9-16-12
 Barton County, Kans.

COMMENCED: March 7, 1945.
 COMPLETED: March 22, 1945.

CASING RECORD:
 8 5/8" casing cemented at 225'
 with 80 sack cement.
 5 3/8" casing cemented 2' off bottom
 with 100 sack cement. TD rotary
 measure 3350'

ELEVATION: 1895
 PRODUCTION: Dry

FORMATION	DEPTH	FORMATION	DEPTH
Surface clay & sand	100	Shale & lime	2710
Shale & shells	225	Lime (Topeka)	2785
Red bed & shells	410	Lime	3350
Shale & shells	680	Total DEPTH ROTARY MEASURE	3350'
Shale & shells	795		
Anhydrite	835	Lansing	3085
Shale & shells	1250		
Salt & shale	1495		
Shale & shells	1845		
Shale & lime	1860		
Lime	2080		

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

Hannum Drilling Co.
Boyd Wright

Subscribed and sworn to before me this 13th day of April, 1945

My Commission Expires March 13, 1948
~~My commission expires 13-4-48.~~

Wm. Wallingford
 Notary Public

LOGGING
 FILE 9 16 124
 BOOK 9 5

APR 15 1945
 APR 25 1945