


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 12 Twp. 21S Rge. 16W(E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Phinney Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed January 10, 1963 19
Application for plugging filed September 27, 1968 19
Application for plugging approved September 27, 1968 19
Plugging commenced October 5, 1968 19
Plugging completed October 10, 1968 19
Reason for abandonment of well or producing formation nonproductive in commercial quantities
If a producing well is abandoned, date of last production September 20 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3782 Bottom 3800 Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	974'	Cemented
				5 1/2"	3784'	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 3788 to 3760 feet. Dumped 5 sacks cement. Mud to 400 feet; 15 feet rock bridge to 385 feet; 6 yards cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.
Address 320 North Park, Stafford, Kansas 67578


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of October, 1968

My commission expires December 10, 1968

Evelyn Wanko
Notary Public.



WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 12-20-62

Contractor: Quaker Drilling Co., Inc.

Completed: 12-31-62

Phinney No. 1
NW NW NW Sec. 12-21S-16W
Pawnee County, Kansas

Elevation: 1971 K.B.

Casing Record

Set 8 5/8 inch casing at 974 feet with 475 sacks cement
Set 5 1/2 inch casing at 3784 feet with 100 sacks cement

(Figures Indicate the Bottom of the Formation)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil	35	Heebner	3324 -1353
Sand and Gravel	60	Brown Lime	3414 -1443
Red Bed, Shale & Shells	400	Lansing	3425 -1454
Sand	510	Base of Kansas City	3671 -1700
Red Bed	965	Viola	3699 -1728
Anhydrite	990	Simpson	3750 -1779
Shale and Shells	1070	Arbuckle	3782 -1811
Red Bed, Shale and Lime	1445	Rotary Total Depth	3788 -1817
Shale and Salt	1685		
Shale and Lime	3110		
Lime	3320		
Lime and Shale	3788		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NW NW Section 12, Township 21 South, Range 16 West, Pawnee County, Kansas.

QUAKER DRILLING CO., INC.

By: _____
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 10th day of January, 1963.

Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1965

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1968
CONSERVATION DIVISION
Wichita, Kansas