


WELL PLUGGING RECORD

Get All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 12 Twp. 21 Rge. 16 ~~16~~ (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C E/2 NE/4 NE/4
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Smith Well No. 1
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Aug. 12, 19 47
Application for plugging filed Sept. 13, 19 51
Application for plugging approved Sept. 14, 19 51
Plugging commenced Sept. 14, 19 51
Plugging completed Sept. 22, 19 51
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production Aug. 10, 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3753 Bottom Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8	115	none
				9"	709	none
				5-1/2	3788'	2055'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back from TD 3790' to 3737' w/crushed rock & 5 sax cement
Shot Casing off 2055' - Pulled Casing
Filled hole with mud to 700' of top.
Pumped in 250 sax Cement to fill surface pipe
Mixed three sax cement for cap on well

STATE CORPORATION COMMISSION
SEP 27 1951
9-27-51
CONSERVATION DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to W. J. Dearen % Anderson-Prichard Oil Corp.
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Gerald M. Dougherty (employee of owner) ~~owner of operator~~ of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Gerald M. Dougherty
Box 142 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 51
Verdella M. Hankins
Notary Public.

My commission expires Dec. 4, 1954

23-5081-s 8-50-10M
PLUGGING
FILE SEC 12 T 21 R 16a
BOOK PAGE 109 LINE 17

SARA SMITH WELL # 1

Location: C. E $\frac{1}{2}$ NE $\frac{1}{2}$ NE $\frac{1}{2}$ Sec. 12-21S-16W
Pawnee County, Kansas

Operator: The Bay Petroleum Corporation

Contractor: H H & B Drilling Co., Inc.

Casing Record: 13" surface casing set at 115'
9" " " " " 709'
and cemented by Magnolia, in 1940
Oil String - 120 Jts. or 3794' of
5-1/2" 8 R.T. 14 $\frac{1}{2}$ cemented
@ 3788 with 150 sacks Ideal
Cement by Sun Cementing Co.

Commenced: 8:00 A.M. 7-5-1947
cleaning out old
Magnolia hole.

Completed: 7-10-47 - 10:00 P.M.

Elevation: 1968 KB

LOG

Cleaning out old hole	0 to	1225
Washing in hole		2650
Reaming		3580
Drilling Cement		3600
Drilling out cement plug		3787
Drilling line (new hole)		3790
Total Depth		3790'

Formation Tops taken from Scout Tickets

Anhydrite	960	(+ 1008)
Lansing	3412	(-1444)
Viola	3694	(-1726)
Simpson	3722	(-1754)
Arbuckle	3764	(-1796)

The undersigned, H H & B DRILLING CO., INC., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H & B DRILLING CO., INC.

BY: Joe J. Horak

Vice-President

Subscribed and sworn to before me this 12th day of August, 1947.

SEP 14 1951

CONSERVATION DIVISION

WICHITA, KANSAS

Richard Hendry
Notary Public

My commission expires: July 2, 1949

PLUGGING

FILE SEC 1878 R162

BOOK PAGE 69 OF 17