


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 13 Twp. 21 Rge. 16 E/W
Location as "NE/CNW/SW" or footage from lines
NW NW NW
Lease Owner Icer Addis
Lease Name Marlett Well No. 1
Office Address P. O. Drawer 8038 Wichita, Kans. 67208
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

Dry Hole
Date Well completed 3-3-78 19
Application for plugging filed 3-3-78 19
Application for plugging approved 3-3-78 19
Plugging commenced 3-3-78 19
Plugging completed 1:15 P. M. 3-3-78 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3809'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with mud-pumped 40 sx common cement thru open end DP
Mud to 40' - 1/2 sack hulls- wood plug for solid bridge
10 sx. to surface - 2 sx in rat hole - 3 sx in water well
By Halliburton

RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1978 3-6-78

(If additional description is necessary, use BACK OF THIS SHEET)
Name of Plugging Contractor _____
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Gary Bagby (employee of owner) or ~~(owner)~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Bagby
Gary Bagby Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 78

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

ICER ADDIS - OPERATOR

MARLETT # 1
NW NW NW 13-21-16W
PAWNEE COUNTY, KANSAST. D. 3809'
ELEV. 1972 KBCOMMENCED: 2-23-78
COMPLETED: 3-3-78CASING

8-5/8" set at 980'

CEMENT

450 sx 50/50 Pozmix, 3% CC

FORMATIONSand & Shale
Dakota Sand
Red Beds
Anhydrite
Shale & Lime
Lime & Shale
DolomiteDEPTH0 - 402
402 - 510
510 - 967
967 - 997
997 - 3100
3100 - 3802
3802 - 3809TOPSDakota Sand
Anhydrite
Heebner
Toronto
Douglas Shale
Brown Lime
Lansing
Base K/C
Viola
Simpson
Arbuckle
RTD402
967
3333
3352
3365
3427
3436
3660
3710
3761
3802
3809RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1978

CONSERVATION DIVISION
Wichita, KansasAFFIDAVITState of Kansas County of BartonI, Gary Bagby of the L. D. DRILLING COMPANY

being first duly sworn on oath, State: That I have knowledge of the facts, statements and matters hereincontained and that the same are true and correct.

Gary Bagby
Gary BagbySubscribed and sworn to before me on this 4th day of March 1978

MY Commission expires: 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81Bessie M. DeWerff
Notary Public: Bessie M. DeWerff