

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee

County. Sec. 13 Twp. 21 Rge. 16 (W) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Nadel and Gussman

Lease Name ~~1714 First National Building~~ Gore Well No. 2

Office Address 1714 First National Building, Tulsa 3, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 12-6-1957

Application for plugging filed 12-6-1957

Application for plugging approved 12-6-1957

Plugging commenced 12-6-1957

Plugging completed 12-6-1957

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	975'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from T.D. to 350' - set plug with 25 sax cement

Set top plug at 40' and cemented to top

*Good  
12-17-57*

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Reserve Drilling Company, Inc.  
Address 625 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. C. Hay (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay

Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December 1957

My commission expires Nov. 3, 1960

Rola Bandy  
Notary Public.

PLUGGING  
FILE SEC 13 T 21 R 16a  
BOOK PAGE 68 LINE 16

Nadel and Gussman

Gore No. 2

NW NW SW 13-21-16W  
Pawnee County, Kans.

Comm: 11-24-57  
Comp: 12-6-57

Casing: 8-5/8" 975' w/450 sax

<u>Formations</u>	<u>Depth</u>
Sand	155
Shale and sand streaks	375
Shale	402
Sand	520
Shale and shells	930
Red bed	967
Anhydrite	998
Shale and shells	1765
Shale, lime, shells	1975
Lime and shale	2160
Lime	2240
Lime and shale	3255
Lime	3322
Lime and shale	3425
Lime	3685
Lime and chert	3770
Lime and shale (cherty)	3807
Lime and shale	3830
Lime	3840
Arbuckle	3850

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF SEDGWICK )

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

*L. C. Hay*

Subscribed and sworn to before me this 9th day of December, 1957.

*Rola Bass*  
Notary Public

RECEIVED  
STATE COMMISSION

Nov. 3, 1960

DEC 17 57

CONSERVATION DIVISION

PLUGGING  
 FILE SEC 13 T 21 R 16W  
 BOOK PAGE 68 LINE 16