


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

Pawnee County. Sec. 13 Twp. 21 Rge. 16 (E) (W)
Location as "NE/CNW%SW%" or footage from lines NE/SE/SE
Lease Owner Nadel and Gussman
Lease Name Gore Well No. #1
Office Address Box 106, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 6-22 1958
Plugging completed _____ 6-27 1958
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3896' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				5 1/2"		3,140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3896'.
Plugging started 6-22-58. Finished 6-27-58.
Plugged off bottom with sand to 3800' and dumped 5 sacks cement.
Shot 5 1/2" casing at 3,140'. Layed down pipe. Mudded to 240'. Set rock
bridge and dumped 20 sacks cement. Filled hole with mud to 40'. Set
rock bridge and mixed 10 sacks cement for cap on well. Well completed.

STAT 3
7-12-58
JUL 12 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of July, 1958
Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 13T.21 R.16W
BOOK PAGE 106 LI E 31

WELL LOG

NADEL AND GUSSMAN

GORR No. 1

NE SE SE 13-21-16W

Pawnee County, Kansas

Comm: 5-26-54
Comp: 6-9-54

Casing: 8-5/8" 966' w/450 sax
5-1/2" 3897' w/100 sax

<u>Formations</u>	<u>Depths</u>
Sand	80
Shale	376
Dakota Sand	496
Shale and red bed of sand streaks	670
Shale and red bed	951
Anhydrite	978
Red bed	1025
Shale and shells	1465
Shale, shells and broken lime	1765
Shale and lime	2075
Lime	2470
Shale and lime	3035
Lime	3340
Lime and shale	3355
Toronto lime	3371
Shale	3434
Brown Lime	3443
White Lime	3465
Lime	3650
Lime and shale	3712
Chert	3758
Shale	3790
Sand	3800
Sandy shale	3813
Dolomite	3897

The Geological Tops


Heebner Shale	3336
Brown Lime	3434
Lansing-Kansas City	3443
Base Kansas City	3650
Viola	3714
Simpson	3758
Arbuckle	3813

3' correction on above tops up the hole.

STATE OF KANSAS

COUNTY OF SEDGWICK

} 85



L. C. Hay, of lawful age, deposes and states that the above depths and formations are correct as shown by the daily drilling log of the Gorr No. 1 in the NE SE SE 13-21-16W, Pawnee County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 15th day of June, 1954.

W. L. Cook

Notary Public

My commission expires Nov. 3, 1956