

15-009-03269-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 9 Twp. 16 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/NE/NE


Lease Owner Four-Way Operating
Lease Name Reck Well No. # 1
Office Address Box 698, Great Bend, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) oil

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-26-79 19
Plugging completed 10-3-79 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	197	none
				4 1/2"	3300'	1515.14'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fished and spudded out bridge at 340' cleaned out to 2400'
Dumped sand to 2850' and 4 sks cement.
Shot pipe at 2400'-2200'-1800' and 1500'
Pulled 48 joints 4 1/2' casing
Squeezed well with 5 sks hulls, 15 sks gel 100 sks
50/50 pozmix cement with 4% added gel.

11-5-79

RECEIVED
STATE CORPORATION COMMISSION
NOV 05 1979
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold, Box 698, Gt. Bend, Ks
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1979

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-28-83

Iona M. Leatherman
Notary Public.

My commission expires _____

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

RECK #1
SE NE NE Sec. 9-16S-12W
Barton County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 10-5-62
Completed: 10-15-62

Casing Record: 8-5/8" @ 197' with 145 sacks Sun Oilwell.
4-1/2" @ 3300' w/135 sack cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			1871 Gr.
Rock	0	196	1873 D.F.
Shale & Sand	196	445	1876 K.B.
Hard Sand with streaks			
Pyrite	445	784	
Anhydrite	784	800	
Shale & Shells	800	1470	
Shale & Lime	1470	2690	
Lime	2690	3275	
Lime & Shale	3275	3304	
Conglomerate	3304	3361	
Total Depth	3361		
			<u>LOG TOPS</u>
			Anhydrite 784 +1092
			Heebner 2944 -1068
			Toronto 2964 -1088
			Douglas 2975 -1099
			Brown Lime 3034 -1158
			Lansing 3046 -1170
			Base Kansas City 3246 -1370
			Conglomerate 3304 -1428
			Total Depth 3361 -1485

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NE NE Sec. 9-16S-12W, Barton County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover

V. Richard Hoover, President

Subscribed and sworn to before me this 17th day of October, 1962.

Carmen Reinhardt Leiker

Carmen Reinhardt Leiker, Notary Public
STATE CORPORATION COMMISSION

My commission expires: Jan. 26, 1963.

SEP 25 1979