

X

4- 090571

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-051-23,299-0001

SW SE NW /4 SEC. 32, 12 S, 19 W
2970 feet from S section line
3630 feet from E section line

Operator license# 31521

Lease: Amrein "A" Well # 2 OWWO

Operator: Kenmark Corporation

County: Ellis

Address: P.O. Box 572
Hays, Kansas 67601

Well total depth 3885 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 256 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 08 Month: August Year: 1998

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone: -

Were: Order 200 sxs 60/40 pozmix - 6% gel.
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:00 A.M., Day: 11, Month: August, Year: 1998

Actual plugging report:
1st. Plug at 1510' w/25 sxs cement.
2nd. Plug at 700' w/100 sxs cement.
3rd. Plug at 250' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.
15 sxs in rathole.
10 sxs in mousehole.
Anhydrite 1503' - Arbuckle - yes.

Remarks: Allied Cementing. Contractor reported mud and impermeably on arbuckle test.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2155 GL

I did[] / did not[X] observe the plugging.

Ed Schumacher
(agent)