

X

4-110032

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,939
15'E. of
SW NE NW /4 SEC. 34, 14 S, 19 W
4290 feet from S section line
3615 feet from E section line

Operator license# 31521
Operator: Kenmark Corporation
Address: P.O. Box 572
Hays, Kansas 67601

Lease: Feitz "A" Well # 4
County: Ellis
Well total depth 3814 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 151 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D.S. & W. Well Servicing License# 6901

Address: 403 Front St. - Claflin, Kansas 67525

Company to plug at: Hour: 11:00 A.M. Day: 15 Month: September Year: 1997

Plugging proposal received from: Mark Kilian

Company: Kenmark Corporation Phone: 316-587-3361

Were: Sand to 3400' w/5 sxs. Shoot pipe at 2000' and run 140 sxs cement with 300# hulls, pull 5 1/2" casing to 1425' and pump 40 sxs with 100# hulls. Pull 5 1/2" casing to 675' and pump 40 sxs cement with 100# hulls. Pull to 150' and pump 30 sxs. Top off with 20 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:00 P.M., Day: 15, Month: September, Year: 1997

Actual plugging report: Perfs at 3457' to 3857'. 8 5/8" casing at 15' with 140 sxs. 5 1/2" casing at 3813' w/165 sxs. Sanded to 3400' w/5 sxs. Shot 5 1/2" casing off at 2300' and pulled 300'. Pumped 140 sxs w/300# hulls. Pulled 5 1/2" casing to 1460' - pumped 40 sxs w/100# hulls. Pulled 5 1/2" casing to 705' - pumped 40 sxs w/100# hulls. Pulled to 165' and circulated cement to top with 50 sxs cement and 100# hulls. October 15, 1997 - Allied pumped additional 30 sxs to top off. Total 300 sxs 60/40 pozmix - 10% gel and 600# hulls.

Remarks: Allied Cementing.
Condition of casing (in hole): GOOD X BAD
Bottom plug (in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: 2118 GL
Anhy. plug: YES X NO
Dakota plug: YES X, NO

I did [X] / did not [] observe the plugging.

Roger Moses
(agent)

HD.