

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

McPherson

County. Sec. 2 Twp. 21 Rge. (E) 2 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SW

Lease Owner J. P. Gaty

Lease Name Scott Well No. 1

Office Address 11 Cyprus Drive, Eastborough, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Oct. 2, 1956 19

Application for plugging filed 10-2-56 19

Application for plugging approved 10-2-56 19


Plugging commenced 10-2-56 19

Plugging completed 10-2-56 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Simpson Depth to top          Bottom 3475 Total Depth of Well 3475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO  | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|-----|-------|--------|------------|
| Surface   | water   | 0    | 282 | 8 5/8 | 282    | None       |
|           |         |      |     |       |        |            |
|           |         |      |     |       |        |            |
|           |         |      |     |       |        |            |
|           |         |      |     |       |        |            |
|           |         |      |     |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

- 3475-280 Fill w/heavy mud
- 280-240 Set good permanent plug, then 1/2 sax hulls, then 15 sx cement thru drill pipe.
- 240-30 Fill w/heavy mud, then good permanent plug, then 1/2 sx hulls, then 10 sx cement to base of cellar.

RECEIVED 10-6-56  
STATE CORPORATION COMMISSION  
OCT 6 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.

Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour James Armour

Shawver-Armour, Inc. 817 Central Building  
(Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 5th day of October 19 56

My commission expires December 29, 1959

Marjorie Hall  
Marjorie Hall Notary Public.

PLUGGING  
FILE SEC F 2 T 21 R 20W  
BOOK PAGE 105 LINE 28

## DRILLER'S LOG

COMPANY: J. P. Gaty LOCATION: NW NW SW  
 Sec. 2-21-2W  
 CONTRACTOR: Shawver-Armour, Inc. McPherson County  
 FARM NAME: SCOTT #1 ELEVATION: 1503 *02*  
 COMMENCED: September 21, 1956  
 COMPLETED: October 2, 1956

## CASING RECORD

282' 8-5/8" w/225' sx 2% cc

| FORMATION                 | TO   |             |      |
|---------------------------|------|-------------|------|
| Sand, Shale & Lime Rock   | 160  |             |      |
| Gray, Shale & Lime Shells | 282  |             |      |
| Lime & Shale Shells       | 375  |             |      |
| Anhydrite, Shale & lime   | 565  |             | TOPS |
| Lime Shale & Red Bed      | 640  |             |      |
| Lime w/Shale Strks        | 810  | Douglas     | 2076 |
| Lime & Shale              | 1045 | Lansaing    | 2307 |
| Shale & Shells            | 1440 | Mississippi | 2956 |
| Shale & Lime Strks        | 1775 | Kinderhook  | 3226 |
| Lime & Shale              | 2060 | Viola       | 3416 |
| Shale w/lime strks        | 2075 | Simpson     | 3447 |
| Sand-Shale                | 2240 | D & A       | 3475 |
| Shale w/lime strks        | 2315 |             |      |
| Lans. lime & Shale        | 2380 |             |      |
| Lime & Shale              | 2475 |             |      |
| Lime w/shale strks        | 2575 |             |      |
| Lime & Shale              | 2918 |             |      |
| Shale & Lime              | 2975 |             |      |
| Miss. Lime Chert          | 3045 |             |      |
| Miss.                     | 3100 |             |      |
| Lime Chert                | 3136 |             |      |
| Miss. Lime                | 3179 |             |      |
| Lime                      | 3207 |             |      |
| Lime & Shale              | 3255 |             |      |
| Shale                     | 3342 |             |      |
| Shale, Dolo. &            | 3415 |             |      |
| Lime & Shale              | 3446 |             |      |
| Simpson Sand              | 3475 |             |      |

STATE OF KANSAS)  
 )ss  
 SEDGWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily driller's report.

By: James Armour  
 James Armour, Sec. Treas.

Subscribed and sworn to before me this 5th day of October, 1956.

Marjorie Hall  
 Marjorie Hall, Notary Public

My commission expires December 29, 1959

