

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
314 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 35 Twp. 21 Rge. 16 (E) (W)

Location as "NE/CNW/SE" or footage from lines. SE NE SE  
Mull Drilling Company, Inc.

Lease Owner: Mull Drilling Company, Inc.  
Lease Name: Prosser Well No. B-6

Office Address: P. O. Box 349 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed \_\_\_\_\_ 10

Application for plugging filed 12-28-70 10

Application for plugging approved 12-29-70 10

Plugging commenced 2-12-71 10

Plugging completed 2-13-71 10

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 10

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4260 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	955	None
				5 1/2	4000	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 900' and dumped 5 sacks of cement. Bailed fluid down to 300'. Dumped 3 sacks of cement on plug at 900'. Bailed fluid to 425'. Pushed wood plug; dumped 10 gallons of sand, 15' rock bridge. Plugged well with 2 1/2 yards of ready mix concrete to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor: Forbes Casing Pulling Company, Inc.  
Address: P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss. James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 24 day of February, 1971

My commission expires May 27, 1973

Notary Public

Well No. 5 Prosser #1  
 Located SE NE SE  
 Sec. 35-21E-16N  
 Pottawatomie County, Kans.

Casing

935' of 2-5/8" OD Surface  
 Casing cemented with 175 cement.

1000' of 5 1/2" OD casing  
 cemented with 1700 cement.

Work Commenced 5/20/54  
 Drilling Commenced 5/20/54  
 Drilling Completed 5/25/54  
 Work Completed 5/27/54

WELL LOG

Sand & Gravel	0	to	100
Sand & Clay	100	to	160
Blue Shale	160	to	310
Red Shale	310	to	405
Sand	405	to	510
Shale & Sand	510	to	615
Red Bed & Shale	615	to	620
Red Bed	620	to	915
Anhydrite	915	to	975
Shale	975	to	1200
Shale & Shells	1200	to	1125
Salt	1125	to	1125
Shale & Shells	1125	to	2035
Lime	2035	to	2040
Shale & Lime	2040	to	3020
Lime	3020	to	3105
Lime & Shale	3105	to	3216
Lime	3216	to	3355
Lime & Shale	3355	to	3509
Lime	3509	to	3619
Conglomerate	3619	to	3850
Cherty Conglomerate	3850	to	3909
Simpson	3909	to	3915
Arbuckle (Top Arb. 3915)	3915	to	4177
Cherty Lime	4177	to	4211
Arbuckle	4211	to	4253 SD

RECEIVED  
 STATE COMMISSION  
 FEB 29 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

CERTIFICATION

State of Oklahoma, County of Tulsa, SS

I, Herrick Babcock, Partner of Iron Drilling Company, certify that the accompanying is a true and correct log of the above described well.

Subscribed to and sworn before me this 7th day of June, 1954.

*B. Michal*  
 Notary Public

My commission expires Feb. 20, 1956