


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 35 Twp. 21 Rge. 16W E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
100' NE SW SW  
Lease Owner Wilson Exploration & Development, Inc.  
Lease Name Hutcherson Well No. 3  
Office Address P. O. Drawer 546, Wilson Kansas 67490  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above Section Plat

Date Well completed Feb. 1 19 79  
Application for plugging filed (verbally) Feb. 1 19 79  
Application for plugging approved (verbally) Feb. 1 19 79  
Plugging commenced Feb. 1 19 79  
Plugging completed Feb. 1 19 79  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3529'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. 3529'  
Set 1st plug at 360' with 50 sacks  
2nd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks.  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 9:40 p.m., 2-01-79.

2-7-79  
RECEIVED  
STATE CORPORATION COMMISSION  
FEB - 7 1979  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 79



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82.

CONTRACTOR'S WELL LOG

15-145-20574-0000

OPERATOR: Wilson Exploration & Development  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Hatcherson #3  
 LOCATION: 100' NE SW SW SW, Section 35-21-16W  
 Pawnee County, Kansas  
 SPUD DATE: January 25, 1979  
 COMPLETION DATE: February 1, 1979

0	193	Sand
193	375	Sand, clay and shale
375	703	Shale
703	1678	Sand and shale
1678	3462	Shale
3462	3529	Shale and sand
	3529	Rotary Total Depth

Spud hole at 5:45, January 25, 1979. Drilled 703' of 12 1/4" hole. Ran 18 joints of 8-5/8" - 28# casing. Set at 700' K.B. with 400 sacks of 50/50 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 5:45 p.m., January 27, 1979.

T.D. 3529'. Set 1st plug at 360' with 50 sacks, 2nd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% Gel. Plug was down at 9:40 p.m., February 1, 1979.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hatcherson #3, 100' NE SW SW SW, Section 35-21-16W, Pawnee County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 6th day of February, 1979.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB - 7 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas