

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

PAWNEE

County. Sec. 35 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Ralph Lynch

Lease Name CADE-HUTCHERSON Well No. 2

Office Address R. R. # 4 Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____


Plugging commenced _____ 6-1 1972

Plugging completed _____ 6-30 1972

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4097 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK TO 3900' WITH SAND.
PUMPED 4 SACKS CEMENT.
PUMPED 3 SACKS HULLS
PUMPED 15 SACKS MUD
PUMPED 100 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1972

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor LYNCH CASING PULLING CO
Address RT 4, GREAT BEND, KS

STATE OF KANSAS COUNTY OF BARTON, ss.
L. RALPH LYNCH (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Lynch

(Address)

SUBSCRIBED AND SWORN TO before me this 31ST day of AUGUST, 1972.

My commission expires 7-18-76

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1972
CONSERVATION DIVISION
Wichita, Kansas

Lehigh Road

RICHARD B. SCHMIDT
1219 COLLEGE AVENUE
TOPEKA, KANSAS 66604

PETROLEUM EXPLORATION CONSULTANT

June 15, 1970

EHRlich DRILLING COMPANY

Wilson, Kansas

Operator -

CADE - HUTCHERSON # 2, the approximate Southwest Quarter of the Southwest Quarter of the Southwest Quarter (SW $\frac{1}{4}$) of Section 35, Township 21 South, Range 16 West, PAWNEE COUNTY, KANSAS.

GENERAL:

Contractor: Ehrlich Drilling Company, Wilson, Kansas

Rotary Drilling: Surface to 4097 feet

Spudded & set surface casing: May 7, 1970

Under surface casing drilling commenced: May 9, 1970

Drilling completed: May 23, 1970 at 1:00 p. m.

Total depth: 4097 feet

CASING:

52 feet of 16 inch casing cemented

Surface pipe: 984 feet of 8 - 5/8 ths cemented with 500 sacks.

Production pipe:

4096 feet of 4 $\frac{1}{2}$ casing cemented with 150 sacks of cement.

ELEVATIONS:

Ground level after dirt work:

Derrick floor:

Rotary bushing: Assumed or estimated at 1980 feet above sea

Rotary bushing elevation and measurements used.

DRILL STEM TESTS:

One (1) by Crown Testing Company, Box 611, Great Bend, Kansas, ticket # 582, May 19, 1970, from 3816 to 3860 feet.

CORES:

NONE

ELECTRIC LOGS:

Gamma Ray - Neutron Radiation and collar log inside of 4 $\frac{1}{2}$ casing by Great Guns, Hays, Kansas, from 4054 to 3390 feet; from 960 to 1006 feet neutron curve only.

15.145-20152-0000

Ray Hunter

PUBLIC ACCOUNTANT
1221 MORPHY STREET
GREAT BEND, KANSAS 67530
AREA CODE 316 - 792-4416

8/31/72

Sec. 35-21-16W
Cade-Hutcherson Well No. 2
SW SW SW

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1972

CONSERVATION DIVISION
Wichita, Kansas

State Corporation Commission
Wichita, Kansas

Re attached notice & report:


Sirs:

I clearly recall dictating & notarizing this report some time ago, and assumed it was surely mailed. Evidently it went astray somewhere along the way. The secretary is no longer with me.

I enclose a duplicate made out to the best of our recollection.

If anything more is required, please contact me direct. Contacting Mr Lynch is difficult & much delayed.

Sincerely,



Ray Hunter.