

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
312 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 35 Twp. 21 Rge. 16 (E) (W) X

Location as "NE/CNW/SE" or footage from lines. SE SE SE
 Lease Owner Mull Drilling Company, Inc.
 Lease Name Prosser Well No. B-2
 Office Address P. O. Box 349 Russell, Kansas 67665
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 10
 Application for plugging filed 12-21-70 10
 Application for plugging approved 12-22-70 10
 Plugging commenced 2-8-71 10
 Plugging completed 2-13-71 10
 Reason for abandonment of well or producing formation
 If a producing well is abandoned, date of last production 10
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation Depth to top Bottom Total Depth of Well 3864 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	958	None
				7	3855	1995', 66

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded off bottom to 3800' and dumped 6 sacks of cement. Shot casing at 3300' and 3210'. Shot casing at 3017', 2607' and 2309'. Laid down 3 joints of casing. Casing hung up. Shot casing at 2113', 2012' and 1915'. Laid down 59 joints of 7" casing. Pushed plug to 375' and dumped 25' rock bridge. Plugged with 7 yards of ready mix concrete to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
 Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
 James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 P. O. Box 221 Great Bend, Kansas 67530
 (Address)

Subscribed and sworn to before me this 24 day of February, 1971



(Signature) Notary Public

My commission expires May 29, 1973

DRILLING RECORD

15.145.01432-0000

Well No. 2 Prosser "B"
 Located SE SE SE of
 Sec. 35-21S-16W, Pawnee
 County, Kansas

Casing Record

962' of 10-3/4" surface pipe
 cemented with 625 sacks.

Work commenced 6/8/52
 Drilling commenced 6/9/52
 Drilling completed 6/24/52
 Work completed 6/25/52

3855' of 7" OD Casing cemented
 with 75 sacks.

WELL LOG

Sand & Shale	0 to	80
Sand & Clay	80 to	140
Shale & Shells	140 to	405
Sand	405 to	500
Shale & Shells	500 to	530
Shale & Sand	530 to	630
Red Bed	630 to	810
Shale	810 to	948
Anhydrite	948 to	978
Shale	978 to	1270
Shale & Shells	1270 to	1800
Shale & Lime	1800 to	2015
Sand & Shale	2015 to	2025
Lime & Shale	2025 to	3185
Lime	3185 to	3431
Lime & Shale	3431 to	3504
Lime	3504 to	3857 TD

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1970
 CONSERVATION DIVISION
 Wichita, Kansas