


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 36 Twp. 21S Rgo. (E) 16 (W)

Location as "NE/CNW&SW" or footage from lines NE SW SE

Lease Owner Barnett Oil, Inc.

Lease Name Prosser Well No. 1

Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) OWWO 67202

Date well completed Mar. 21 19 72

Application for plugging filed Jan. 21 19 75

Application for plugging approved 19

Plugging commenced Feb. 13 19 75

Plugging completed Feb. 21 19 75

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3912 feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			945'	8 5/8"	945'	none
			3912'	4 1/2"	3912'	2868.11

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3850' and dumped 4 sacks of cement.

Set 20' rock bridge at 325'. Plugged well with 5 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1975 2-27-75

Name of Plugging Contractor PIPE PULLERS, INC. (If additional description is necessary, use BACK of this sheet)

Address Box 128, Ellinwood, Kansas 67528 CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth

(employee of owner) or (owner-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas

SUBSCRIBED AND SWORN TO before me this 26th day of February 19 75

My commission expires

GEORGE A. MEYER
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. FEB. 10, 1979

(Address) Searge A Meyer
Notary Public.

KANSAS DRILLERS LOG

API No. 15 — 145 — 20238-0001
 County Number

S. 36 T. 21 R. 16^{XX}
 W

Loc. C S 1/2 SE

County Pawnee

Operator
Barnett Oil Co.

Address
411 First Nat'l Bank Bldg., Wichita, Kansas. 67202


Well No. #1 Lease Name Prosser OWWO

Footage Location
990 feet from XX (S) line 990 feet from XX (W) line

Principal Contractor Red Tiger Drilling Co. Geologist Alfred W. Stude

Spud Date 12-7-71 Re-entered 3-18-72 Total Depth 3912 P.B.T.D.

Date Completed 3-21-72 Purchaser Kansas-Nebraska
 Gas



Elev.: Gr. 1971
 Locate well correctly

Dr. 1973 kb. 1976

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	945'		500	
		4 1/2"	9.5#	3912	Posmix	125	18% salt; 3/4% CFR2 w/1/8# nylon fibre per sks.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
			8		3900 - 3900 1/2'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
 STATE CORPORATION COMMISSION
 APR 21 1975
 CONSERVATION DIVISION
 Wichita, Kansas

INITIAL PRODUCTION

Date of first production <u>4/2/72</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>10</u> bbls. Gas <u>1.430</u> MCF Water <u>-0-</u> bbls. Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	Producing interval(s) <u>Simpson</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Barnett Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas
Well No. 1	Lease Name Prosser O W W O	
S. 36 T. 21 R. 16 ^{XXX} W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>See report filed previously covering dry hole completed 12/18/71.</p> <p>Re-entered 3-18-72 - took Straddle test: 3899-3903 - 0 - 60"; SI - 60"; 0 - 120"; SI - 60"; immediate strong blow, GTS in 1"; gauged 1/4 mmcf, increased to 2.8 mmcf in 60". Second opening gauged 3.1 mmcf, increased to 3.7 mmcf rec. 90' free oil, 40"; 10' water. IFP - 204# ISIP - 1273# FFP - 427# FSIP - 1245#</p>				

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1975
CONSERVATION DIVISION
Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	BARNETT OIL COMPANY
	By: _____ Signature
	Partner _____ Title
	August 30, 1973 _____ Date