

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
314 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Pawnee County, Sec. 36 Twp. 21 Rge. 16 (E) (W) X

Location as "NE/CNWSW" or footage from lines SW SW SW

Lease Owner Mull Drilling Company, Inc.

Lease Name Prosser Well No. B-1

Office Address P. O. Box 349 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 12-21-70 19

Application for plugging approved 12-22-70 19

Plugging commenced 1-20-71 19

Plugging completed 2-15-71 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3917 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	672	None
				5 1/2	3909	3068', 08

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3840'; dumped 20 gallons of sand and 5 sacks of cement. Shot casing at 3187' and 3090'. Pulled casing 99 joints of 5 1/2". Squeezed well with 2 sacks of hulls, 20 sacks of gel and 100 sacks of 50/50 pozmix cement with 6% gel added.

2-26-71

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 24 day of February, 1971



(Signature) Notary Public

My commission expires

DRILLING RECORD

Well F. Prosser "B" #1
 Located SW SW SW Sec. 36-21S-16W
 Pawnee County, Kans.

Casing Record

687' of 8-5/8" OD Surface Pipe
 cemented with 350 sacks.
 3909' of 5 1/2" OD Casing
 cemented with 100 sacks

Work Commenced 12/10/51
 Drilling Commenced 12/11/51
 Drilling Completed 12/31/51
 Work Completed 12/31/51

WELL LOG

Sand & Surface Clay	0 to 105
Sand & Shale	105 to 145
Shale & Shells	145 to 405
Sand	405 to 515
Red Bed	515 to 755
Anhydrite	755 to 790
Shale & Shells	790 to 1585
Shale & Lime	1585 to 1645
Shale	1645 to 1790
Shale & Lime	1790 to 1805
Lime	1805 to 1945
Lime & Shale	1945 to 2150
Lime	2150 to 2230
Shale & Lime	2230 to 3505
Lime	3505 to 3527
Shale & Lime	3527 to 3530
Lime	3530 to 3785
Conglomerate	3785 to 3875
Simpson	3875 to 3910
Lime	3910 to 3917 TD

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1970
 CONSERVATION DIVISION
 Wichita, Kansas