

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Return to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 36 Twp. 21 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Iron Drilling Company

Lease Name Prosser Well No. 5

Office Address 1206 Philtower Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 6-16-51 19

Application for plugging filed 10-1-56 19

Application for plugging approved 10-1-56 19

Plugging commenced 10-1-56 19

Plugging completed 10-7-56 19

Reason for abandonment of well or producing formation Oil exhausted

If a producing well is abandoned, date of last production 7-1-56 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Arbuckle Depth to top 3906 Bottom 3936 Total Depth of Well 3936 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Brown Lime		3475'		8-5/8"	642'	None
Kansas City		3483'		5-1/2"	3936'	2214'
Conglomerate		3775'				
Simpson		3848'				
Arbuckle		3906'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand Bridge set to 3905'. Cement plug run from 3905' to 3875' - 5 sacks cement. Casing pulled. Surface hole squeezed with 100 sacks cement, 25 sacks of mud and 2 sacks calcium chloride. Halliburton cement trucks used.

CONSERVATION DIVISION
WICHITA, KANSAS
10-23-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Casing Pulling Co.

Address Box 192, Ellinwood, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Herrick Babcock (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herrick Babcock

1206 Philtower Bldg., Tulsa 3, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 1956

B. Michal
Notary Public.

My commission expires Feb. 28, 1960

PLUGGING
FILE SEC. 36 T. 21 R. 16W
BOOK PAGE 103 LINE 36

DRILLING RECORD

Casing Record

Well No. 4 Prosser
 Located SW SW SE of Sec. 36-21S-16W
 Pawnee County, Kansas

642' of 8-5/8" OD Surface
 pipe cemented with 350 sacks.

Work Commenced 5/3/51
 Drilling Commenced 5/4/51
 Drilling Completed 5/21/51
 Work Completed 6/16/51

3936' of 5 1/2" OD Casing cemented
 with 150 sacks

WELL LOG

Surface Sand & Shale	0 to 105
Sand	105 to 190
Blue Shale	190 to 415
Sand	415 to 520
Red Bed	520 to 942
Anhydrite	942 to 972
Shale & Shells	972 to 1290
Salt & Shale	1290 to 1480
Shale & Shells	1480 to 1520
Lime & Shale	1520 to 2060
Lime	2060 to 2080
Lime & Shale	2080 to 2165
Lime	2165 to 2338
Lime & Shale	2338 to 2460
Lime	2460 to 2540
Lime & Shale	2540 to 2600
Lime & Shale Streaks	2600 to 2675
Lime & Shale	2675 to 2990
Lime	2990 to 3066
Shale & Lime	3066 to 3148
Lime (Top K.C. 3483)	3148 to 3777
Cherty Conglomerate	3777 to 3838
Lime & Chert	3838 to 3843
Shale	3843 to 3870
Shale & Sand	3870 to 3904
Shale	3904 to 3906
Arbuckle	3906 to 3927
Lime	3927 to 3936 TD

STAT

COU

PLUGGING
 FILE SEC. 36 T. 21 S. 16W
 BOOK PAGE 103 LINE 36