

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Pawnee County, Sec. 28 Twp. 21 Rge. 16 (E) (W)

Location as "NE/CNW/SW" or footage from lines. NW SW SE

Lease Owner Murfin Drilling Company

Lease Name Crawford Well No. 1

Office Address 910 Union National Bk. Bld. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 10 19 53

Application for plugging filed December 10 19 53

Application for plugging approved 19


Plugging commenced December 10 19 53

Plugging completed December 10 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Reives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3860 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged from 3860' to 300' with rotary mud; from 300' to 240' with 20 sacks of cement through drill pipe; from 240' to 40' with rotary mud; from 40' to -0- with 10 sacks of cement.

Job completed at 5 o'clock A.M. December 10, 1953

RECEIVED

STATE CORPORATION COMMISSION

MAR 18 1954

3-18-54

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor United Drilling, Inc.

Address Mohl Building, 814 Maple St., Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.

Clyde D. Kinsinger (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clyde D. Kinsinger  
814 Maple St. Russell  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 53

Marlene Zook  
Notary Public.

My commission expires 10-30-57

PLUGGING  
FILE SEC 28 T 21 R 16 W  
BOOK PAGE 149 LINE 8

15-145-00065-0000

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Murfin Drilling Company**


SEC. **28** T. **21** R. **16**

FARM **Crawford** NO. **1**

LOC. **NW SW SE**

TOTAL DEPTH **3860'**  
COMM. **Nov. 28, 1953** COMP. **Dec. 10, 1953**  
SHOT OR TREATED  
CONTRACTOR **United Drilling, Inc.**  
ISSUED

COUNTY **Pawnee**  
KANSAS



CASING

20 10  
15 8 **5/8"** 986 feet  
12 .6  
13 5

ELEVATION

PRODUCTION **Dry Hole**

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:

Clay, Sand, and Shale	-0-	feet	Heebner	3400 - 1396
Shale	392	"	Toronto	3419 - 1415
Sand	430	"	Brown Lime	3498 - 1494
Shale and shells	530	"	Lansing	3508 - 1504
Red Bed	635	"	Congl.	3821 - 1817
Anhydrite	983	"	Simpson	3836 - 1832
Red Bed, Shale, Shells	1015	"	Arbuckle	3855 - 1851
Shale and shells	1250	"	R. T. D.	3860 - 1856
Lime and shale	1820	"		
Shale and shells	2715	"		
Shale and lime shells	2890	"		
Shale and lime	2985	"		
Lime	3255	"		
Lime and shale	3395	"		
Shale	3440	"		
Lime	3500	"		
Shale and lime	3790	"		
Lime	3855	"		
Total Depth	3860	"		

I certify that this is the true and correct copy of the above log, to be correct to the best of my knowledge.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1954

CONSERVATION DIVISION

Wichita, Kansas

*Clyde G. Kissinger*  
Clyde G. Kissinger  
President of United Drilling, Inc.

Subscribed and sworn to before me this 30th day of Dec., 1953.

*Marlene Zook*  
Notary Public

My commission expires 10/30/57

PLUGGING  
FILE SEC 28 T 21 R 16W  
BOOK PAGE 149 LINE 8