

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Pawnee County, Sec. 28 Twp. 21 Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Hewson Well No. 1
Office Address 522 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 11-17-58 19
Application for plugging filed 11-18-58 19
Application for plugging approved 11-18-58 19
Plugging commenced 11-18-58 19
Plugging completed 11-18-58 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1012	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Push plug to 950, cement w/15 sax thru d.p. Fill w/mud to 240, hulls, plug, 20 sax thru d.p. Fill w/mud to 35, hulls, plug, 10 sax.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1958

My commission expires June 4, 1959

Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
11-20-58
NOV 20 1958
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 20 T 21 R 16W
BOOK PAGE 146 LINE 35

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Hewson
NW NW NE, Sec. 28-21-16W,
Pawnee County, Kansas

Elevation 2020 KB
D & A
Set 1012' of 3 5/8" w/425 sax

Commenced: 11-7-58
Completed: 11-17-58
Contractor: Rupp-Ferguson Oil Co.

Figures Indicate Bottom of Formation

- 45 clay & surface soil
- 190 sand & clay
- 307 blue shale
- 430 sand streaks, rock & shale
- 552 Dakota
- 1005 red bed
- 1032 Anhydrite
- 1090 red shale
- 1600 red shale, shells & salt
- 1760 shale
- 2170 lime & shale
- 2295 shale, sand & lime
- 2328 lime
- 2420 lime & shale
- 2503 lime & sand streaks
- 3330 lime & shale
- 3418 shale, sand streaks & lime
- 3545 lime & shale
- 3779 lime
- 3832 lime & shale
- 3861 lime, shale, chert
- 3873 lime, shale & sand
- 3880 Arb.

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

I, L. W. Knox, Partner in Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Hewson well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 19th day of November, 1958.

Helen Forester
Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires June 4, 1959.

NOV 20 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 28 T. 21 R. 16W
BOOR PAGE 146 LINE 35