

Well Log
Sinclair Prairie Oil Co.

James E. Ely # 1..
AE #216
Location made 8/25/1944.
NW/4 SE/4, 30-21-28W Finney Co. Kas.
330 ft fm Nth & West lines
Elev. 2749'

Harbar Drlg Co. rotary
Began drlg 12/10/1944..5:00PM
Completed drlg 1/27/1945
Run 389 ft 9-5/8"OD 32# H40 new
csg set at 386' w/175 sx cnt.
Run 1940 ft 7"OD 24# SS 10thd SH
csg set at 1916' w/375 sx cnt
TD 4866'

Drillers Log

Clay	40
Blue Shale	65
Shale	175
Shale & Shells	300
Sand	350
Shale-Lime	394
Shale & Shells	600
Sand	735
Shale	790
Shale & Shells	910
Sand	1075
Shale	1125
Sand	1155
Shells & Shale	1200
Red Bed	1880
Red Bed & Shells	1897
Lime	1930
Shale & Shells	1960
Lime	2010
Shale-Shells	2077
Lime	2097
Shale-Lime	2290
Shale & Shells	2390
Lime-broken	2590
Broken Lime-Shale	2670
Broken Lime	2725
Shale & Lime	2770
Lime	2955
Shale	2980
Broken Sand	3000
Shale	3010
Lime-	3290
Lime-sandy	3390
Lime	3420
Shale & Lime	3455
Lime	3595
Lime & Shale	3635
Lime-broken	3687
Lime	3725
Lime-broken	3780
Lime	3842
Lime-broken	3875
Lime	3990
Shale	4000
Lime	4625
Cherty-lime	4628
Lime	4725
Lime-cherty	4750
Lime	4795
Lime-hard	4805
Chert-rough	4835
Lime	4866

PLUGGING
FILE 30 21-28W
BOOK PAGE 6 LINE 2

After set 7" csg run 3" drill pipe in to within 10 ft of bottom and lost circulation which was unable to regain even after putting in a large amount of cement, drilling mud, alfalfa hay, etc. Gave up, and well plugged & abandoned. 2/28/1945..

No record of any tops of formations .