

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-185 30077-0000

Operator's Full Name Hamilton & Satterthwaite

Complete Address: 710 Union National Bldg., Wichita, Kansas

Lease Name Helsel Well No. # 1

Location SE SW NE Sec. 19 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4016'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: H-30 Drilling, Inc.

Address: 200 North Main, Wichita, Kansas License No.

Operation Completed: Hour 12:30 PM Day 26th Month June Year 1965

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
level in the hole was at 30'. 1st cementing plug and 1 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Fluid level was now at 35', 1st cementing plug, bridged
solid with dry cement and hulls on fluid at 35', and cemented with
8 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED JUN 28 1965

Signed: Archie Ebling
Well Plugging Supervisor

DATE 6/28/65 CONSERVATION DIVISION

INV. NO. 1373-W Wichita, Kansas