

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1964

CONSERVATION DIVISION
Wichita, Kansas

15-185-19461-0000

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Oklahoma Fracturing Service Inc.

Complete Address: 302 Bettles Bldg., 1501 Classen Blvd., Oklahoma City, Okla.

Lease Name Dietz Well No. # 1

Location SW SW SW Sec. 20 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3850

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co., Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30PM Day 1st Month Feb. Year 1964

The Above well was plugged as follows:

284' of 8 5/8" surface pipe, cemented with 265 sacks. 3849' of 5 1/2" long
string, with 600 gal. of Latex. Plug back to 3760'. Top perforation 3714',
Bottom of hole was sanded to 3700', and cemented with 5 sacks. Hole was
flowing with water and a squeeze job was necessary. 15 sacks of Gel-Mud
and 80 sacks of cement, was pumped into surface pipe, through an 8 5/8"
swage, to a pressure of 150 lbs.
3103' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/6/64

INV. NO. 8525-W