

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Co., Inc.
Complete Address P. O. Box 349 Russell, Kansas 67665
Lease Name Prosser Well No. B-6
Location SE NE SE Sec. 35 Twp. 21 Rge. (E) (W) 16
County Pawnee Total Depth 4260'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well XX D & A _____
Other well as hereafter indicated _____
Plugging Contractor Forbes Casing Pulling Co.
Address Box 221 Great Bend, Kansas 67530 License No. 637
Operation Completed: Hour 1:30 P Day 13 Month 2 Year 1971

The above well was plugged as follows:

Total Depth 4260' 8 5/8 csg set at 955' cwc 475 sk.
5 1/2 csg set at 4000' cwc 1700 sk.
5 1/2 csg PBTD 900' No pipe recovered.
pushed 5 1/2 wood plug to 900' -poured 10 gal sand and dumped 3 sk cmt W/dump bailer.
Mid to 425' -set rock bridge and dumped 2 1/2 yds readymix cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/17/71
INV. NO. 3348-W

Signed: Leo P. Mussey
Well Plugging Supervisor