

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ralph Lynch

Complete Address R. R. # 4 Great Bend, Kansas

Lease Name Cade - Hutchinson Well No. 2

Location SW SW SW Sec. 35 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 4097'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No. 457

Operation Completed: Hour 6 P Day 6 Month 3 Year 1972

The above well was plugged as follows:

Total Depth: 4097' 16" set at 45' cwc: 8 5/8 csg set at 984' cwc:

4 1/2 csg set at 4096' cw 150 sk cmt.

Set 4 1/2 wood plug at 3500' -poured 15' sd' -dumped 4 sk cmt W/dump bailer. (3450-3500)

Cutoff and recovered 3105' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 100 sk 50-50 poz .

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob F. Massey
Well Plugging Supervisor

DATE 3-10-72

INV. NO. 5316-102