


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-185-30059-0000

STAFFORD County. Sec. 18 Twp. 23S Rge. (E) 14 (W)

Location as "NE/CNW&SW" or footage from lines. SW SW SE
Lease Owner GLENN N. RUPE AND HOWARD A. STOSKOPF
Lease Name REDETZKE Well No. 1
Office Address 222 BROWN BLDG. - WICHITA, KANSAS 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 28, 19 65
Application for plugging filed JUNE 1, 19 65
Application for plugging approved MAY 28, 19 65
Plugging commenced MAY 28, 19 65
Plugging completed MAY 28, 19 65
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4090 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	270	8-5/8"	270'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 265 FEET. SET FIRST PLUG @ 265 FT. WITH 1/4 SACK HULLS AND 25 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG @ 40 FT. WITH 1/4 SACK HULLS AND 10 SACKS CEMENT. CAPPED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG. - WICHITA, KANSAS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG. - WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1ST day of JUNE, 19 65

My commission expires FEBRUARY 1, 1968

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

GABBERT-JONES INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

15-185-30059-000

REDETZKE #1
 SW SW SE SECTION 18-23S-14W
 STAFFORD COUNTY, KANSAS

COMMENCED: MAY 21, 1965
 COMPLETED: MAY 28, 1965

OPERATOR - GLENN N. RUPE AND HOWARD A. STOSKOPF

DEPTH		FORMATION	REMARKS
FROM	To		
0	30	CLAY	
30	130	SAND	
130	185	CLAY	
185	270	CLAY	RAN 12 JOINTS 8-5/8" CASING, SET @ 270 FT. w/275 SX. CEMENT.
270	375	RED BED AND SHALE	
375	430	SAND	
430	900	RED BED AND SHALE	
900	940	ANHYDRITE	
940	1380	SHALE AND SHELLS	
1380	1675	SHALE AND LIME	
1675	1785	LIME AND SHALE	
1785	2350	LIME	
2350	2520	SHALE AND LIME	
2520	2940	LIME AND SHALE	
2940	3155	SHALE AND LIME	
3155	3325	SHALE AND LIME	
3325	3593	LIME AND SHALE	
3593	3820	LIME	
3820	3940	LIME AND SHALE	
3940	3975	LIME	
3975	4023	LIME WITH CHERT	
4023	4090	SANDY SHALE LIME	
4090	TD		DRY AND ABANDONED.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 3 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SW SW SE SECTION 18-23S-14W, STAFFORD COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 1ST DAY OF JUNE, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968