

15-185-21401-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County. Sec. 18 Twp. 23 Rge. 14W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C W/2 NE  
Lease Owner Allen Drilling Company  
Lease Name TANNER Well No. 1B  
Office Address P.O. Box 1389, Great Bend, KS 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
dry hole



Locate well correctly on above  
Section Plat

Date Well completed 9/26 1981  
Application for plugging filed 9/26 1981  
Application for plugging approved 9/26/1981  
Plugging commenced 9/26 1981  
Plugging completed 9/26 1981

Reason for abandonment of well or producing formation \_\_\_\_\_  
dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bud Metz  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4100'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	298'	8-5/8"	298'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

50/50 poz., 2% gel, 3% cc.:  
60 sks @ 690'  
40 sks @ 290'  
10 sks @ 40'  
10 sks in rathole  
plug down 9AM, 9/26/81

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1981

(If additional description is necessary, use BACK of this report)  
Name of Plugging Contractor Allen Drilling Company  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
Greg Davidson (employee of owner) or (owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Greg Davidson  
P.O. Box 1389, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1981



Ruth Brack  
Notary Public.

My commission expires \_\_\_\_\_

DRILLER'S WELL LOG

15-185-21401-0000

DATE COMMENCED: 9/18/81  
DATE COMPLETED: 9/26/81

ALLEN DRILLING COMPANY  
TANNER No. 1B  
C W/2 NE  
Sec. 18, Twp. 23S, Rge. 14W,  
Stafford County, Kansas

ELEVATION: 1969' G.L.  
1974' K.B.

FORMATION DATA:

2896 -	Anhydrite
3113 - 3434'	Lime
3434 - 3456'	Shale
3456 - 3474'	Lime
3474 - 3567'	Shale
3567 - 3578'	Lime, shale
3578 - 3812'	Lime
3812 - 4032'	Lime, shale
4032 - 4081'	Sand
4081 - 4100'	Dolomite
4100'	RTD

Anhydrite	896'
Topeka	3113'
Heebner	3434'
Toronto	3456'
Douglas	3474'
B.Lime	3567'
Lansing	3578'
B K.C.	3812'
Simpson	4032'
Arbuckle	4081'
RTD	4100'

SURFACE DATA:

Ran 7 jts new 20# 8-5/8"  
casing; tally: 291'  
Set @ 298' w/ 250 sks 60/40  
pos., 2% gel, 3% cc., plug  
down 5:45 P.M. 9/18/81  
(cemt. circulated)  
By Howco

PLUGGING DATA:

60 sks @ 690'  
40 sks @ 290'  
10 sks @ 40'  
10 sks in rathole  
50/50 poz., 2% gel, 3% cc.  
Plug down 9 AM, 9/26/81  
By Howco; Bud Metz, Suprvsr

A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1981

CONSERVATION DIVISION  
Wichita, Kansas

Greg Davidson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Greg Davidson

Subscribed and Sworn to before me this 6th day of October, 1981.

  
RUTH BRACK  
State of Kansas  
My Appt. Exp. 7/21/84

Ruth Brack  
Notary Public