


15-185-01093-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County. Sec. 18 Twp. 23 Rge. 14 (E) W(W)
Location as "NE/CNW%SW%" or footage from lines NE SW NW
Lease Owner Prime Drilling Company
Lease Name Tanner Well No. 1
Office Address 814 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 7 19 60
Application for plugging filed November 7 19 60
Application for plugging approved November 7 19 60
Plugging commenced November 7 19 60
Plugging completed November 7 19 60
Reason for abandonment of well or producing formation no oil and/or gas found
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4105 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 240'. Set Plug #1 and 20 sacks cement.
Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R-R. McNicol
814 Union Center, Wichita, Kansas
Nov. 15 (Address) 60, 1960

SUBSCRIBED AND SWORN to before me this _____ day of _____, 1960
My commission expires Sept. 30, 1963

Darlene May
Darlene May Notary Public.



NOV 23 1960
CONSERVATION DIVISION
Wichita, Kansas

11-23-60

ROTARY DRILLING LOG

15-185-01093-0000

OPERATOR: Prime Drilling Company
TANNER NO. 1
NE SW NW Sec. 18-23-14W
Stafford County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 10/28/60
COMP: 11/7/60

Remarks: Set 8-5/8" (270' set at 277')
cemented with 225 sacks cement

Formations:

Sand	60'
Shale	278'
Shale & Red Bed	360'
Sand	420'
Red Bed	900'
Anhydrite	945'
Shale & Lime	1870'
Lime	2340'
Lime & Shale	3365'
Shale & Lime	3470'
Lime & Shale	3580'
Shale	3590'
Lime	3977'
Cherty Lime	4021'
Lime & Shale	4092'
Arbuckle	4105'
Rotary Total Depth (D&A)	4105'

We certify the above log is true and correct
to the best of our knowledge and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION
NOV 23 1960
CONSERVATION DIVISION
Wichita, Kansas