


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD 15-185-20230-0000

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 19 Twp. 23S Rge. (E) 14 (W)
Location as "NE/CNW/SE" or footage from lines NW SW SE
Lease Owner Oklahoma Fracturing Services, Inc.
Lease Name Kackelman Well No. 3
Office Address 630 United Founders Life Tower, 5900 Mosteller Dr. Okla. City
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 6 19 69
Application for plugging filed November 6 19 69
Application for plugging approved November 6 19 69
Plugging commenced November 6 19 69
Plugging completed November 6 19 69
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Depth to top Bottom Total Depth of Well 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED	STATE CORPORATION COMMISSION		8 5/8"	271'	none
	NOV 20 1969	CONSERVATION DIVISION				
	Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 100 sacks of 50/50 Poxmix, 6% Gel

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address P.O. Box 486, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James Rodgers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Rodgers
James Rodgers
P.O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19 th day of November 19 69

Notary Public

My commission expires October 19, 1972

DRILLER'S LOG

15-185-20730-0000

COMPANY: Oklahoma Fracturing Services, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: KACKELMAN #3
 LOCATION: NW SW SE SECTION 19-23S-14W
 STAFFORD COUNTY, KANSAS
 COMMENCED: 10-31-69
 COMPLETED: 11-6-69

0	170	Clay-Sand
170	272	Shale
272	845	Red Bed & Sand
845	906	Red Bed
906	926	Anhy
926	1500	Shale & Shells
1500	1740	Shale & Lime
1740	2290	Lime
2290	3060	Shale & Lime
3060	3200	Lime & Shale
3200	3345	Lime & Shale Stks
3345	3810	Lime
	<u>3810</u>	<u>RTD D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1969
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" .24# used surface casing set at 271' cemented with 270 sacks
 Common Cement, 2% Calcium Chloride.

I, James Rodgers, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Kachelman #3 Well, located
 NW SW SE of Section 19, Township 23 South, Range 14 West, Stafford
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

James Rodgers
 James Rodgers

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 19th day of November, 1969.

Clayton Mottet Benoit

Commission Expires:
 October 19, 1972