


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 19 Twp. 23 Rge. 14 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner Woodman & Iannitti Oil Company
Lease Name Miller Well No. 1
Office Address 706 Union National Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 6-11-68 19____
Application for plugging approved 6-12-68 19____
Plugging commenced 6-12-68 19____
Plugging completed 6-14-68 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	196	None
				5 1/2	None	3312
RECEIVED STATE CORPORATION COMMISSION JUN 19 1968 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 3750'. Dumped 5 sacks of cement. Rigged up unit. Working pipe. Shot pipe at 3325'. Pulling pipe.

Bailing water. Pushed plug to 195' rock bridge. Dumped 8 sacks of cement.

Bailing & Plugging. Dumped 18 sacks of cement. Mudded hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of June, 1968.

My commission expires May 27, 1969

Notary Public.

15-185-20073-0000

Company; Woodman & Iannitti Drilling Company
Location NW. SW NW
Section; 19-23-14
County; Stafford
Farm Name; Miller No. 1
Comm; November 10, 1967
Comp; November 18, 1967
Total Depth; 3845'
Contractor; Woodman & Iannitti Drilling Company
Casing; 8 5/8" at 196 w/120 sacks
5 1/2" at 3844' w/100 sacks

Figures Indicate Bottom Of Formations

30	Clay
90	Sand
160	Clay & Sand
196	Blue Shale
355	Shale
410	Sand
914	Red Bed
950	Anhy
1185	Shale
1740	Salt, Shale & Shells
1945	Lime & Shale
2055	Lime
2155	Lime
2275	Lime
2410	Lime & Shale
2525	Lime
2715	Lime
2955	Lime & Shale
3110	Lime
3235	Lime
3380	Lime
3480	Lime
3563	Lime
3615	Lime
3730	Lime
3760	Lime
3830	Lime
3835	Lime
3845	Lime

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1968
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Company

K. T. Woodman
K. T. Woodman