

original

15-113-20432-0000

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Call or Deliver Report to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

McPherson County, Sec. 12 Twp. 21S Rge. 2W (E) (W)
 Location as "NE/C WSWX" or footage from lines NE SE
 Lease Owner Chas W. Sanders Oil Co.
 Lease Name Dyck Well No. 1
 Office Address 603 N. Edgemoor, Wichita, Kansas
 Character of Well (Completed as Oil, Gas or Dry Hole) dry
 Date well completed 5-23-77 19
 Application for plugging filed 5-23-77 19
 Application for plugging approved 5-23-77 19
 Plugging commenced 5-23-77 19
 Plugging completed 5-23-77 19
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 200' set plug 25 sks cement
Fluid to 40' set plug 10 sks cement
2 sks. cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1977 7-26-77


(If additional description is necessary, use back of this form)
 Name of Plugging Contractor Triangle Drilling Co. Wichita, Kansas
 Address 901 S. Denver, El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler

Harry Hughes

I, Harry Hughes, employed by Triangle Drilling Co. (owner/operator) of the above-described well, being duly sworn on oath, say: That I have known the contents of the above-described well as filed and that the same are true and correct. I hereby certify that the same are true and correct.

(Signature) Harry Hughes
Harry Hughes
901 S. Denver, El Dorado, Kansas 67042



Subscribed and Sworn to before me this 24 day of May, 1977
Nov. 11 1980

Juanita Hughes
Juanita Hughes Notary Public.

My commission expires

WELL LOG

Operator Chas W. Sanders Oil Co.
 Comm Comp
 Shot Qts. From ft. To ft.
 Acidized Gal.
 Prod. Formation
 Initial Prod.
 Elevation

Lease Dyck Well No. 1
 Loc ENE SE Sec 12 Twp 21S Rge 2W
 County McPherson State Kansas
 Contractor Triangle Drilling Co.

Casing Record			
Size	Ft.	Pulled	Remarks
8 5/8	181	175	sks cement

FIGURES INDICATE BOTTOM OF FORMATION

0	-----	181	Surface
181	-----	781	Shale
781	-----	1040	Shale & Lime
1040	-----	1335	Shale
1335	-----	1682	Shale & Lime Stks
1682	-----	1885	Shale & Lime
1885	-----	2343	Shale
2343	-----	2542	Lime KC
2542	-----	2626	KC
2626	-----	2720	K.C. Lime
2720	-----	2984	Lime & Shale
2984	-----	3034	Miss
3034	-----	3136	Miss Lime
3136	-----	3245	Miss
3245	-----	3288	Miss Lime
3288	-----	3303	Miss
3303	-----	3396	Kinderhook
3396	-----	3417	Minser
3417	-----	3440	Hunton RTD

RECEIVED
 STATE COMMISSION

JUL 26 1977

CONSERVATION DIVISION
 -Wichita, Kansas-