

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County. Sec. 13 Twp. 21 Rge. (E) 17 (W)

Location as "NE/CNW/SE" or footage from lines NW NW SE

Lease Owner John P. Jennings, et al

Lease Name Hewson Well No. 1

Office Address 917 Minnesota Avenue - Kansas City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 16 19 56

Application for plugging filed May 16 19 56

Application for plugging approved May 16 19 56


Plugging commenced May 16 19 56

Plugging completed May 16 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation - Depth to top _____ Bottom _____ Total Depth of Well 3880 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1038'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300'; set first plug with 20 sacks cement and 1/3 sacks of hulls.

Filled hole with heavy mud to 35'; set second plug with 10 sacks cement and 1/3 sacks of hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.

Address McBride Building - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
JIM B. McWILLIAMS (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams

McBride Building - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1956

Mary O. Johnson
Notary Public.

My commission expires November 21, 1959

24-7568-5 3-53-20M

PLUGGING
FILE SEC. 13 T. 21 R. 17W
BOOK PAGE 62 LINE 30

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

5-23-56

DRILLERS LOG

Company: John P. Jennings, et al Location: NW NW SE
Contractor: Strata Drilling, Inc. Section 13-21S-17W
Farm Name: Hewson #1 Pawnee County, Kansas
Commenced: May 5, 1956 Elevation: 2038' KB; 2033' GL
Completed: May 16, 1956 Casing: 1038' 8-5/8" 24# Casing

0 -	35	Surface Soil and Sand
	460	Red Bed and Shale
	565	Sand
	895	Shale and Shell
	1023	Shale
	1033	Anhydrite
	1355	Red Bed
	1795	Shale, Shell and Salt
	2230	Lime and Shale
	2290	Lime
	2475	Shale and Shell
	3445	Lime and Shale
	3850	Lime
	3875	Shale and Lime

Total Depth 3875' KB

STATE OF KANSAS)
) SS.
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

STRATA DRILLING, INC.

J. B. McWilliams

J. B. McWILLIAMS

Subscribed and sworn before me this 22nd day of May, 1956.

Mary O. Johnson

Mary O. Johnson Notary Public
STATE CORPORATION COMMISSION

My Commission expires November 21, 1959

PLUGGING
FILE SEC. 13 T. 21 R. 17W
BOOK PAGE 62 LINE 30

RECEIVED
MAY 22 1956
CONSERVATION DIVISION
Wichita, Kansas