

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 18 Twp. 21S Rge. (E) 17 (W)

Location as "NE/CNW/SE/SW" or footage from lines NE NW NW
Lease Owner Pickrell Drilling Company
Lease Name Froetschner "C" Well No. 1
Office Address 705 Fourth National Bank Bldg, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 22, 19 68
Application for plugging filed February 22, 19 68
Application for plugging approved February 22, 19 68
Plugging commenced February 22, 19 68
Plugging completed February 22, 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 450'. Set plug. Cemented with 90 sacks
cement. Heavy mud to 10'. Set plug. Cemented with 10
sacks cement to bottom of cellar. Plugged rat hole with
2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. Sebitts (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th Natl Bk Bldg, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of March, 19 68



L. M. Whiting
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 2/12/68

Rotary Drilling Completed 2/22/68

LOCATION: Froetschner "C" No. 1
NE NW NW Section 18-21S-17W
Pawnee County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (14 jts.) 8 5/8" surface casing set at 273' and cemented with 170 sacks of cement. Circ. Complete @ 10:00 PM, February 12, 1968. No oil string was run. D. & A., plugged February 22, 1968.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil	C. F. S.
273	Shale, Shells & Sand Streaks	<u>3577'</u>
450	Shale	3610'
545	Red Beds	3630'
685	Sand	3650'
1110	Red Beds & Shale	3655'
1133	Shale	3708'
1160	Anhydrite	3740'
1950	Shale	3758'
2310	Lime & Shale	3785'
2390	Lime	3815'
3680	Lime & Shale	3825'
3830	Lime	3925'
3890	Lime & Shale	3940'
3940	Lime, Shale & Sand	3950'
3950	Sand & Chert	3960'
3965	Sand	3965'
3980	Lime & Chert, RTD	3980'

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Slope Tests
2500'
3000'
3500'

S. L. M.
3588.29'
Board
Strap 3586.60'
Diff. 1.69'

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 1st day of March, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identified person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
Notary Public
L. M. Whiting

