

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Must or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County, Sec. 18 Twp. 21 Rge. (E) 17 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW 1/4 SW 1/4

Lease Owner: Cities Service Oil Company

Lease Name: Evans Well No. 1

Office Address: Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: May 24 1942

Application for plugging filed: May 30 1942

Application for plugging approved: May 30 1942

Plugging commenced: June 1 1942

Plugging completed: June 5 1942

Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: C. T. Alexander

Producing formation: Arbuckle Depth to top: Bottom: Total Depth of Well: 4038 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
Reagan Sand	Sulfur Water	3896	3901	13" OD	102'	None
				8-5/8"	1084'	None
				5-1/2"	4038'	3189'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total depth of well 4038 ft. Plugged back to 4000 ft. with cement. The hole was filled with chat from 4000 ft. to 3900 ft., bridged and cemented to 3870 ft.; mudded to 300 ft.; a permanent bridge was placed at 300 ft. and cemented to 280 ft.; hole was mudded to 26 ft., cemented to 6 ft., and mudded to surface.

6-26-42

pd.
6/23/42
18 21 17W
37 2



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: R. C. Hauber
Address: Box 751, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. A. Deffeyes (employee of owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of June, 1942

My Commission Expires Sept. 20, 1942

Notary Public.

My commission expires



WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Evans
 Location 990' North and 330' West of 1/4 Corner Sec. 18 T. 21 R. 17W
 Elevation 2091 County Rawlens State Kansas
 Drlg. Comm. April 19, 1942 Contractor Helm Drilling Company
 Drlg. Comp. May 18, 1942 Acid None
 T. D. 4034' Initial Prod. Dry - Plugged and Abandoned

CASING RECORD:

12-1/2" @ 98' con. 100 ex Red King & 2 ex Aquagel
 8-5/8" @ 1025' con. 400 ex Ash Grove
 5-1/2" @ 4034' con. 100 ex 1-ohigh; pulled 3159' of 5 1/2".

FORMATION LOG:

surface rock & sand 0-87
 lime med. 98
 shale & shells 330
 shale 425
 shale & shells 488
 sand & shells 550
 sand 625
 shale red 670
 sand 685
 shale red. 729
 sand 734
 shale red 885
 shale red & shells med. 1057
 shale red 1075
 lime 1108
 shale 1145
 shale dark & shells 1470
 shale blue sandy 1590
 shale blue & shells 1740
 shale, salt & shells 1810
 lime light med. 1840
 shale & shells 1910
 lime light med. 2030
 lime broken med. 2050
 lime light hard 2120
 lime dark hard 2143
 lime med. 2163
 lime broken med. 2275
 lime light hard 2320
 lime broken med. 2390
 lime light med. 2620
 lime light broken 2655
 lime light med. 2820
 lime broken 2858
 lime light med. 2905
 lime broken 2964

lime light med. 3012
 lime broken 3025
 lime light hard 3338
 lime light med. 3405
 lime light hard 3454
 lime light med. 3481
 lime broken 3538
 lime 3608
 lime soft 3622
 lime hard 3655
 lime light med. 3738
 lime light hard 3799
 lime light med. 3848
 lime light hard 3860
 lime light med. 3922
 shale blue 3990
 shale grey, hard 4007
 shale grey soft 4026
 lime 4028
 granite 4038 T.

4038 Rot. TD = 4034 61M

Corr. Top Reagan 3892'
 Corr. Top Granite Wash 4007'
 Corr. Top Granite 4028'
 Penetration 6'
 Total Depth 4034'

Top cement 4000' 61M. May 23, 1942, perf. with 11 shots 3890-3900. 2400' sulphur water in 1/2 hour 2700' sulphur water in 3/4 hour.

500' 0", 1000' 0", 1500' 0", 2000' 0", 2500' 0", 3000' 0", 3500' 10"

FILE
 18 21 17W
 37 2

STATE OF KANSAS
 JUN 26 1942
 REGISTERED
 10