

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

15.145.20363-0000
WELL PLUGGING RECORD
K.A.R.-82-3-117

AMENDED
API NUMBER 15-145 20363-0000

LEASE NAME Prusa
WELL NUMBER # 1-18
SPOT LOCATION C W/2 SE/4
SEC. 18 TWP. 21 RGE. 17 (7) of (W)
COUNTY Pawnee
Date Well Completed 2/26/75
Plugging Commenced 9-24-84
Plugging Completed 10-1-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR InterNorth, Inc.
ADDRESS P. O. Box 35288, Tulsa, Ok 74135
PHONE # (918) 665-9544 OPERATORS LICENSE NO. 9632

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? No If not, is well log attached? With application

Producing formation Herrington-Krider Depth to top 2,035' bottom T.D. 2145'
Winfield
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------------|-----------|--------|------|--------|--------|------------|
| | Anhydrite | 1,083' | 120' | 8-5/8" | 837' | None |
| Herrington-Krider | | 2,035' | 145' | 4-1/2" | 2145' | 1,335.42' |
| Winfield | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 1990' and 4 sacks cement. Shot casing at 1350'. Pulled 30 joints of 4-1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement 2% added gel and 3% calcaim chloride. Maximum pressure was 350 psi and shut in 110 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1984
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-84

Iona M. Leatherman
Notary Public

My Commission expires:

