

State of Kansas



15.145.20048.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 705 4th Nat'l Bk. Bldg. Wichita, Ks.

Lease Name: Froetschner "C" Well No. 1

Location: NE NW NW Sec. 18 Twp. 21 Rge. 17 (E)(W) X

County Pawnee Total Depth 3980 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and displace  
90 sc cement thru drill pipe. Heavy mud to 40' set cementing plug and  
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent