

KANSAS

15-009-03298-
0000FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- ✓200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co.
Complete Address P.O. Box 287, Great Bend, Ks. 67530
Lease Name Woydzish Well No. 3
Location C-5/2 NW NE Sec. 12 Twp. 16 Rge. 12 (East) (West)
County Barton Total Depth 3322'
Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Ks. 67524 License No.
Operation Completed: Hour: 2:30 PM Day: 17 Month: 8 Year: 1982
Plugging Operations attended by Agent?: All X Part None

The above well was plugged as follows:

8 5/8" - 766' S.P. Casing w/ common cement. 5 1/2" set at 3317' w/100 sacks.
Common. Plug back cast iron plug at 3055'. Top perf. at 2876'.
Shot pipe 9 times & recovered 684'. Ordered 150 sacks 50 per sack - 4 1/2
Gel. - 32.6 lb. lb., 5 sacks hulla, 15 sacks Gel. & 8 5/8" plug. Pumped into
S.P., 4 sacks hulla, 12 sacks Gel., 70 sacks cement, 3 sacks Gel., 1 sack
hulla, released plug & followed w/80 sacks cement.

Maximum pressure 800 pounds.
Amount of Surface Casing: 766' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed:
Conservation Division Agent

INVOICED

DATE 8-31-82INV. NO. 993-WRECEIVED
AUG 24 1982
STATE CORPORATION COMMISSION
Wichita, Kansas