



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 1 1959

CONSERVATION DIVISION  
 Wichita, Kansas

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date May 10, 19 59, authorized the following plugging operation:

Operator's Full Name: Donald C. Slawson

Complete Address: 502 Central Bldg., Wichita, Kansas

Lease Name: Schroeder Well No. 1

Location: NE-NE-SW Sec. 10 Twp. 21 Rge. 1 (E) (W) X

County: McPherson Total Depth: 3494

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 190' with heavy mud.  
Push plug and 1/4 sack hulls to 190' and cement with 20 sacks thru  
drill pipe. Fill hole to 40' with heavy mud. Set solid bridge  
and cement with 10 sacks. Fill, bridge, and cement rathole with  
2 sacks.

Very truly yours,

Signed [Signature]  
 Conservation Division Agent