

State of Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

15-009-15743-0000 FORM - CP-2
State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this
date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Nick Well No. # 3

Location: NE SW SW Sec. 12 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3326 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

No surface pipe. Set bottom plug @ 2900' & 5 sax cement with dump
bailer. Pulled pipe. Run tubing to 315'; circulated hole with
mud. Pulled a joint of tubing & displaced 50 sax cement thru
tubing @ 290' with pump truck. Pulled remaining tubing; set
rock bridge @ 25' & run 25 sax cement, cementing to base of
cellar.

Very truly yours,

Don. Tramm
Conservation Division Agent