



15-009-15742-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1965
07-22-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Nick Well No. # 2

Location: C NL SE SW Sec. 12 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3332 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

No surface pipe. Old cable tool hole.

Set bottom plug @ 2700' & displaced 5 sax cement with dump bailer. Pulled pipe. Run 2" tubing to 340'; circulated hole with mud; displaced 40 sax cement thru tubing with pump truck @ 300'. Pulled tubing. Set rock bridge @ 30' & displaced 40 sax cement, cementing to base of cellar.

John T. ...
Conservation Division Agent