



15.113-20584-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

September 30, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT - 6 1978

10-6-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rogers of Kan Co, Inc. has this date requested permission to plug the following described well:

Mr. Rogers guarantees payment of the plugging fee.

Operator's full Name: National Development Co.

Complete Address: 200 W. Douglas, Suite 635, Wichita, Kansas

Lease Name: Goering Well No. 1

Location: C NW SW Sec. 4 Twp. 21 Rge. 1 (W) X

County: McPherson Total Depth 3033' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rogers was instructed to plug the well as follows:

8 1/2" - 228' - 150 sacks Fill hole with mud to 220'. Push plug and 1/2 sack hulls to 220' and cement hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge cathole and cement with 2 sacks.

Very truly yours,


Conservation Division Agent