

District Plugging Report

API Well Number: 15-059-01616-00-00
 SE
 Spot: NENESW Sec 22 Twp 18 S Rng 21 ☒ E / ☐ W
2299 Feet from ☐ N / ☒ S Line of Section
2724 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.468780 Long: 95.075230 Date: 5/8/17 3/22/17
 Lease Name: Nelson Well #: NEL 01
 County: Franklin Total Vertical Depth: 580 feet

State: KS Zip Code: 67202 1513

String	Size	Depth	Pulled	Comments
DRIVE - Drive Pipe	8.000	20	0	EST
L1 - Liner 1	4.500	580	0	EST
T1 - Tubing 1	2.000	570	570	

Company Name: KWS **Phone:** (620) 431-8945

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Report:

KCC Agent: Frank Guilfoyle

Perfs:	Top	Bottom	Thru
	75	350	TBG - Tubing

Clear around location, trees and pump jack. Pull rod and 2" pipe. The 2" was tight, stuck in mud. Perforate well. Run 1" to 580 ft and hit. Pump Portland cement to surface. Pull pipe and top off well. Pump total of 78 sacks of cement. Well plugged. 75

Contract # 38595. Control # 20170032-001. GPS'ed NAD 83 by FG. Reg section.

Plugged Due to Compliance Issue: ☐ Yes ☐ No

CONSERVATION DIVISION
WICHITA, KS

Frank Brillo
(Technician)

Form: District Plugging Report -