

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-185-11043-00-00
 Spot: SWSWSW Sec/Twnshp/Rge: 35-25S-12W
339 feet from S Section Line, 4960 feet from E Section Line
 Lease Name: SLADE Well #: 3
 County: STAFFORD Total Vertical Depth: 4395 feet

Operator License No.: 32457
 Op Name: ABERCROMBIE ENERGY, LLC
 Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4083		
CIBP		4260		
PROD	5.5	4270	0	WITH 225 SX CMT
SURF	8.625	664		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2017 9:00 AM
 Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
 Proposal Revd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: LOAD & TEST CASING. PERFORATE AT 700' WITH CMT TO 0'. SQUEEZE PERFS WITH 50 SX CMT & 200# HULLS.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 05/08/2017 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

RUN IN HOLE WITH 2 3/8" TBG TO 3550' & PUMPED 50 SX CMT WITH 200# HULLS & 3% CC. POOH WITH TBG & WAIT ON CMT 1.5 HOURS. PLUG WAS TAGGED AT 3338'. CASING WAS PRESSURED TESTED TO 300 PSI FOR 5 MINUTES. PERFORATE AT 700'. TIH WITH TBG TO 700'. ESTABLISH CIRCULATION BOTH INSIDE & OUTSIDE 5 1/2" CASING. PUMP CMT TO SURFACE BOTH INSIDE CASING & ANNULUS BETWEEN 5 1/2" & 8 5/8" CASING. TOOK 195 SX CMT. POOH WITH TBG & TOP OFF CASING & ANNULUS WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4040	4075		
3626	3634		
3590	3598		

INVOICED
 MAY 31 2017

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY OES PRESSURE PUMPING.

Plugged through: TBG

District: 01

Signed [Signature]
 (TECHNICIAN)

RECEIVED
 MAY 17 2017
 KCC DODGE CITY