

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-091-19230-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 17-13S-23E
3345 feet from S Section Line, 652 feet from E Section Line
Lease Name: METROPOLITAN L. I. CO. Well #: 2
County: JOHNSON Total Vertical Depth: 378 feet

Operator License No.: 31769
Op Name: ATMOS ENERGY CORPORATION
Address: 1200 11TH AVE
GREELEY, CO 80631

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
PROD	8.625	320		
SURF	0	0		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2017 12:00 PM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JERRY SHAFFER Company: ATMOS ENERGY CORPORATION Phone: (620) 496-6784

Proposed Plugging Method: At this time production casing and surface casing sizes are unknown and will be identified during plugging activities. Determine status of well, if necessary pump mud to kill mud. Trip in 1 or 2 inch tubing to total depth. Flush well with fresh water to clean hole. Circulate cement to surface. Top off with cement after tripping out. This well is located in close proximate to high voltage power lines, if a rig is unable to setup up on the well an alternative plugging plan will be submitted.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 02/24/2017 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

DRILLED DOWN INSIDE THE CASING FROM 10' TO 320'. CLEANED THE WELL OUT WITH GEL FROM 320' TO SURFACE. RAN 2" TUBING DOWN TO 320' AND PUMPED 165 SACKS OF CEMENT TO THE SURFACE.

RECEIVED
KCC DIST # 3
MAY 22 2017
CHANUTE, KS

TH

Remarks: THIS WELL WAS ORDERED TO BE PLUGGED BY THE WICHITA LEGAL STAFF.

Plugged through: TBG

KCC WICHITA
MAY 25 2017
RECEIVED

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOLVED
MAY 24 2017

Form CP-2/3